



F .No. 7/1(1)/2022-23/SD/EMU
Date: - 10.05.2022

इन्दिरा गांधी राष्ट्रीय कला केन्द्र
सूत्रधार

INDIRA GANDHI NATIONAL CENTRE FOR THE ARTS
Sutradhara

Janpath, New Delhi-110 001
Tel.: 91-11-23388280
Website : www.ignca.nic.in

Subject: - Covering the passage behind the Staff Quarter, IGNC New Delhi
Notice Inviting Quotation

Sealed percentage rate quotations are invited on behalf of Indira Gandhi National Centre for the Arts (IGNCA), New Delhi for the work mentioned above.

Quotations duly filled signed and sealed as mentioned in Schedule of quantity (Annexure - A) shall be submitted manually in the office of the under Secretary, Estate Management Unit, IGNC, Janpath Building New Delhi-110001 by **11.05.2022 on or before 03:00 pm.**

The terms & conditions are applicable on above mentioned work as mentioned on Annexure – B.


10/5/2022
Bijender

Under Secretary (EMU)

Subject:-Covering the Passage behind the staff quarter,IGNCA New Delhi

S.no.	Description of Item	Qty	Unit	Rate	Amount
1	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	70	Sqm	671.55	47008.5
2	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :Gutter (600 mm over all girth)	35	mtr	1110.6	38871
3	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finished seamless type tubes	400	kg	168.95	67580
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand)	3	cum	8288.35	24865.05
5	CEMENT PLASTER (IN COARSE SAND) 13.4 12 mm cement plaster of mix : 13.4.1 1:4 (1 cement: 4 coarse sand) sqm	20	sqm	294.85	5897
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	20	sqm	123.85	2477
7	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives.New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	20	sqm	154.45	3089
8	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding kg	200	kg	181	36200
9	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm ²), counter sunk head, comprising of 10 mm dia polyamide PA 6 grade sleeve, including drilling of hole in frame , concrete/ masonry, etc. as per direction of Engineer-in-charge.10 x 80 mm each	50	Nos	117.3	5865
	Total Civil				231852.55
	Electrical				18000
	Grand Total				249852.55
	Quoted Percentage (Above/below)				
	Grand Total				

Terms & Conditions:-

1. The work shall be executed as per CPWD specification.
2. **No secured advance etc. shall be paid or allowed to the contractor.**
3. The rates quoted by the vendor are including of all Taxes/GST etc and nothing shall be paid on account of any taxes what so ever.
4. In the case of Extra Item(s) & substituting items being the schedule items (Delhi Schedule of Rates items), these shall be paid as per the schedule rate (approved in CPWD) (at the time of NIQ) enhancement or abutment of the NIQ.
5. The vendor will have to observe all the prevalent laws including contract labor laws, safety laws etc.
6. No escalation on account of increase of labor wages or material is admissible.
7. No reimbursement is admissible on account of levy of any tax etc.
8. If contractor or his worker damages any property of the IGNCA, the recovery will be made from the contractor as decided by the Engineer-In- Charge, and decision of Engineer -In-Charge is final and binding.
9. All the safety rules should be followed by the Engineer/Technicians of the firm while working in IGNCA, Institute has no liabilities in case of any accident/mishap.
10. **Vendor warrants that all Products, at the time of execution of work will conform with all written specifications provided from time to time by Engineer – in – charge, (b) will be free of defects in material, workmanship, and design, and (c) will comply with all applicable laws and regulations.**
11. The IGNCA reserves the right to reject any material if not found satisfactory.
12. The payment will be made after satisfactory completion of above mentioned work.
13. Final amount will be calculated after the completion of the aforesaid work as per actual measurement.
14. Please also note that the scope of work may be reduced from the estimated quantities and no claim on this account will be entertained.
15. Please also note that if the scope of work increased from the estimated quantities then, the payment will be done as per quoted rate.
16. The Quotations duly filled as mentioned in Schedule of quantity (**Annexure - A**) and signed and sealed and the sealed quotation shall be submitted manually in the office address of The Under Secretary, Estate Management Unit, IGNCA, New Delhi-110001

Name :.....
 Designation :.....
 Company with Seal :.....
 Address :.....
 :.....