



F.No. 7/1(31)/2022-23/SD/EMU  
Date: - 21.02.2023

इन्दिरा गांधी राष्ट्रीय कला केन्द्र  
सूत्रधार

INDIRA GANDHI NATIONAL CENTRE FOR THE ARTS  
Sutradhara

Janpath, New Delhi-110 001  
Tel.: 91-11-23388280  
Website : www.ignca.nic.in

Subject: - Installation of Tableau-Art Within IGNC premises, New Delhi –reg.

**Notice Inviting Quotation**

Sealed percentage rate quotations are invited on behalf of Indira Gandhi National Centre for the Arts (IGNCA), New Delhi for the work mentioned above.

Quotations duly filled signed and sealed as mentioned in Schedule of quantity (Annexure - A) shall be submitted manually in the office of the under Secretary, Estate Management Unit, IGNC, Janpath Building New Delhi-110001 by **24.02.2023 on or before 03:00 pm.**

The terms & conditions are applicable on above mentioned work as mentioned on Annexure – B.

*bl*  
*21/2/2023*

(Bijender)

Under Secretary

Indira Gandhi National Centre for the Arts, New Delhi					
Estate Management Unit					
Subject: Estimate for MoC Tableau-art Installation at various locations with-in Janpath hotel building, IGNC, New Delhi-reg.					
S.no.	Description of Item	Qty	Unit	Rate	Amount
1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.	250	KG	154.9	38725
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	3	cum	6882.00	20646
3	CEMENT PLASTER (IN COARSE SAND) 12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	10	sqm	307.25	3072.5
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	20	sqm	131.45	2629
5	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent sqm	10.00	sqm	3908.80	39088.00
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	2.00	cum	6670.25	13340.50
7	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	20	sqm	123.85	2477.00
8	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer.	20	sqm	162.55	3251.06
9	Cutting and Refixing of cement fiber board by applying arolite or similar adhesive compound and as per the direction of Engineer-in-charge.	10	sqm	500	5000.00
Total					128229.06
Quoted Rate(Above/Below)					
Total					



## ANNEXURE – B

### Terms & Conditions:-

1. The work shall be executed as per CPWD specification.
2. **No secured advance etc. shall be paid or allowed to the contractor.**
3. The rates quoted by the vendor are including of all Taxes/GST etc and nothing shall be paid on account of any taxes what so ever.
4. In the case of Extra Item(s) & substituting items being the schedule items (Delhi Schedule of Rates items), these shall be paid as per the schedule rate (approved in CPWD) (at the time of NIQ) enhancement or abutment of the NIQ.
5. The vendor will have to observe all the prevalent laws including contract labor laws, safety laws etc.
6. No escalation on account of increase of labor wages or material is admissible.
7. No reimbursement is admissible on account of levy of any tax etc.
8. If contractor or his worker damages any property of the IGNCa, the recovery will be made from the contractor as decided by the Engineer-In- Charge, and decision of Engineer -In-Charge is final and binding.
9. All the safety rules should be followed by the Engineer/Technicians of the firm while working in IGNCa, Institute has no liabilities in case of any accident/mishap.
10. **Vendor warrants that all Products, at the time of execution of work will conform with all written specifications provided from time to time by Engineer – in – charge, (b) will be free of defects in material, workmanship, and design, and (c) will comply with all applicable laws and regulations.**
11. The IGNCa reserves the right to reject any material if not found satisfactory.
12. The payment will be made after satisfactory completion of above mentioned work.
13. Final amount will be calculated after the completion of the aforesaid work as per actual measurement.
14. Please also note that the scope of work may be reduced from the estimated quantities and no claim on this account will be entertained.
15. Please also note that if the scope of work increased from the estimated quantities then, the payment will be done as per quoted rate.
16. The Quotations duly filled as mentioned in Schedule of quantity (**Annexure - A**) and signed and sealed and the sealed quotation shall be submitted manually in the office address of The Under Secretary, Estate Management Unit, IGNCa, New Delhi-110001

Name :.....  
Designation :.....  
Company with Seal :.....  
Address :.....  
:.....