

# INDIRA GANDHI NATIONAL CENTRE FOR THE ARTS

SOUTHERN REGIONAL CENTRE, BANGALORE

## SCHEDULE – ‘B’

Name of work: Addition and alterations to Open Air Theatre and Raking area in IGNC/SRC at Bangalore, near AIT Jnanabharathi post Bangalore.

Item No.	Description	Unit	Qty	Rate	
				In figures	In words
1.	Earth work in rough excavation, banking excavated earth in layers not exceeding 20cm in depth, breaking clods watering, rolling each layer with 1/2 tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead up to 50m and lifts up to 1.5m – All kinds of soil.	Cum	13.00		
2.	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge.	Cum	1.10		

Prof. S. Settar  
Director (Hon.)  
IGNCA SRC  
Bangalore

3.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level - 1:4:8 ( 1Cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal).	Cum	9.50		
4.	Brick work with modular bricks of class designation 75 in foundation and plinth in: cement mortar 1:6 ( 1 cement : 6 coarse sand).	Cum	21.00		
5.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level - 1:3:6 ( 1Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal)	Cum	2.10		
6.	12mm cement plaster of mix 1:3(1cement: 3 coarse sand finished with a floating coat of neat cement (with black oxide)etc., complete.	Sqm	39.00		
7.	Extra for pre finished nosing in treads of steps of sadarahalli granite stone flamed finish slab etc., complete.	Rmt	141.00		
8.	Providing and laying 1st quality granite slab feather finish floor tiles 300 x 300mm ( thickness to be specified b the manufacturer ) in colours white, Ivory, gray Fume red, Brown, Black laid on 20mm thick cement mortar 1:4 ( 1 cement: 4 coarse sand ) including pointing the joints with white cement and matching pigment etc., complete.	Sqm	152.50		

Prof. S. Settar  
Director (Hon.)  
IGNCA SRC  
Bangalore

9.	Providing and fixing 1st quality granite slab leather finish wall tiles (thickness to be specified by the manufacturer )of approved make in all colours, shades any size as approved by Engineer-in-charge in skirting, riser of steps and dados over 12mm thick bed of cement mortar 1:3 ( 1cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	12.00		
10.	Providing & fixing 1st quality Sadarahalli/equivalent granite stone slab flamed finish flooring over 20mm (average) thick base laid over and jointed with gray/white cement slurry mixed with pigment to match the shade of the slab with base of cement mortar 1:4 ( 1 cement: 4 coarse sand )	Sqm	122.00		

Prof. S. Settar  
Director (Hon.)  
IGNCA SRC  
Bangalore